

Critical Aspects of Designing Controls for a Reliable Microgrid



Jason Wittkamp
Director



Topics of Discussion

Overview

Controls Hardware

Network Architecture

I/O Type

Factory Testing

Q&A



THERMO SYSTEMS
INDUSTRIAL AUTOMATION & INFORMATION


www.thermosystems.com

Overview

Integration and Controls Challenges

- Uptime
- Multiple OEMs
- Each Project is Unique
- Optimization Complexity
- Cybersecurity and Remote Monitoring Requirements
- Limited Opportunity For Real World Testing

The Microgrid Control System
is Key to Project Success




Graphic Reference:

<https://energycenter.org/self-generation-incentive-program/business/technologies/microgrid>

Hardware Selection

- Controls hardware needs to be industrial grade
 - Consider redundancy
- Standardize if possible
 - Maximize compatibility across systems
- Microgrid controller must accommodate communication protocols of OEMs



Hardware Selection – Case Studies


MP Minerals

- 25 MW cogeneration plant
- Generating assets, power management system (PMS), and electrical gear standardized to single industrial grade platform
 - All communications cabling and hardware are fault tolerant
- Systems natively communicate with each other at high speed (~100 ms updates)
 - No need for third party translators
- Reduce spare parts inventory, software licenses, and maintenance personnel training expenses


Network Architecture

- Segregate Networks
 - Layers (corporate, SCADA, controllers, I/O)
 - DMZs
 - Separate communication protocols (ethernet, Modbus, DNP3, etc.)
- Managed Ethernet Switches/Routers
 - Limit collisions
 - Fault recovery
- Redundant topology
 - Ring over star
- Cybersecurity
 - Designated Network Administrator


Star topology



Ring topology



Network Architecture Example



I/O Considerations

Hardwired



Use For Information
required For Control
Decisions

Pros

- Reliability
- Speed
- Failsafe

Cons

- Electrical Installation Cost
- Additional Hardware

Communicated



Use For Monitoring
Information
(Trending)

Pros

- Cost effective

Cons

- Can have longer update times
- Less reliable

I/O Considerations – Examples

Citibank Financial Services HQ Microgrid

- Hardwired
 - Switchgear open/close commands and position feedback
 - E-Stop circuits
 - Voltage/Frequency Raise/Lower commands
- Communicated
 - Electrical data (kw, kvar, PF, etc..)
 - Fault and trip descriptions, non-critical alarm status



Sequence of Operations (SOO)

- The coordination and optimization of generating assets and loads should be well defined during the design phase
- Equipment vendors need to be aware of their role in the larger SOO scheme
- Schedule regular coordination meetings between the microgrid controller and equipment vendors



SOO - Example

TWA Hotel

- Off grid JFK airport hotel facility with onsite CHP plant
- Reciprocating engines with battery storage and emergency diesel generator
- SOO was well defined in design phase allowing customer to select vendors with proper capabilities.
 - Unique requirements due to the nature of the load and the off-grid status of the microgrid



Factory Testing

Extensive, Coordinated Factory Testing is Critical

- Include OEMs, utility interface, and microgrid controller
- Working out issues in the field leads to quick fixes and band aids
- Decrease startup and commissioning time spent in the field
- Uncover and eliminate showstoppers
- Some test scenarios may be difficult or impossible to schedule
- Every project is unique



Factory Testing - Example

Hudson Yards Cogen

- New mixed-use development on east side of Manhattan
- Interconnect agreement and plant size required extensive interface (< 100 points) with local utility (Con Ed)
- Single day between Thermo Systems and Con Ed allowed for communication between systems and I/O mapping to be verified.
- Reduced startup and commissioning time onsite to less than 1 week.
- Onsite commissioning required commissioning agent, owner, electrical installer, Con Ed, and TS personnel. Reduced commissioning time = savings.



Key Takeaways

- Proper MG controller hardware selection required for smooth integration and resilient microgrid.
- Control system network architectures are complex and cannot be overlooked. Require ongoing maintenance.
- Coordinated factory testing of the control systems minimizes delays during commissioning and increases project success

Key Takeaways

- Upfront planning leads to a more tightly coordinated, optimized microgrid solution.
- Investing in a strong, well thought out microgrid control scheme and sequence of operations during the design phase is key to a successful project.

Q&A

Questions?

THANK YOU!

Jason Wittkamp

Director

Thermo Systems LLC

Jason.Wittkamp@thermosystems.com