



# ENERGY CENTER MINNEAPOLIS CONTROL SYSTEM UPGRADE

# Control System Upgrade at Energy Center Minneapolis

---

- System Historical Overview
- Project Drivers
- Project Options Considered
- Selected Project Scope
- Project Schedule
- Project Implementation
- Project Cost
- New System Key Facts
- Lessons Learned
- Questions

## System Overview

---


- Steam, Hot Water and Chilled water district energy system
- Commenced Operations in 1972
- Serves the downtown business core in Minneapolis MN plus two remote plants
- Three steam plants, one hot water plant, six chilled water plants
- 10 Boilers, 17 chillers
- Purchased steam from two Hennepin County plants
- Electric, steam turbine, and gas engine drive chillers
- Natural gas/#2 Fuel Oil boilers
- 660,000 lb/hr peak steam demand
- 30,000 Ton peak cooling demand

## System Historical Overview - DCS


---

- Bailey Infi90 DCS System Installed in 1980's
  - System installed in five plants
  - One plant connected via coax, two DSL, one stand alone
  - Redundant Controllers and HMI's, Non-Redundant I/O
  - Multiple Controller and HMI Upgrades made over time.
- Allen Bradley PLC Systems Installed in mid 1990's
  - Systems installed in two plants
  - Same family but different age/version controllers
  - Connected via Fiber
  - Non-redundant controllers and HMI's, Non-Redundant I/O
  - No controller and HMI upgrades made over time.
  - Primarily used for HVAC, support systems and as communications interface to local vendor controls






## Overview – Current Configuration



# Project Drivers

- 1980's vintage Core DCS system that had been periodically upgraded was reaching true economic end of hardware and software life.
- Software and equipment maintenance costs increasing
- Loss of experienced technical support personnel
- HMI servers reaching end of life
- Multiple systems/vendors that need to communicate
- Level of investment required to bring current system up to date significant enough to justify evaluating complete or partial replacement with alternate vendors
- Access advanced control, monitoring, diagnostic, and record keeping capabilities of newer DCS systems



## Main Project Options Considered – Core DCS System

---

1. Upgrade/Replace Controllers, Power Supplies and HMI's with current manufacturers most current compatible products. (keep I/O and backplane)
2. Upgrade/Replace Controllers, Power Supplies and HMI's with alternate manufacturers compatible products. (keep I/O and backplane)
3. Upgrade/Replace Controllers, I/O, Power Supplies and HMI's with current manufacturers most current compatible products (keep I/O Backplane)
4. Upgrade/Replace Controllers, I/O, Power Supplies and HMI's with alternate manufacturers compatible products (keep I/O Backplane)
5. Replace Controllers, I/O, Power Supplies and HMI's with current manufacturers most current product.
6. Replace Controllers, I/O, Power Supplies and HMI's with alternate manufacturers most current product newer DCS systems



## Project Options Considered – Other Components

---


- Establish Communications with Fairview Riverside Plant
- Replace everything with same as rest of the system or retain existing Allen Bradley PLC Control Systems (Main Plant HVAC & Fuel Oil, Foster House, Macy's)
- Retain existing coax, replace with fiber-optic, or switch to DSL communications for Convention Center Plant
- Install fiber optic or switch to DSL for 1<sup>st</sup> Avenue Plant
- Include new BMS systems in project scope
- Include instrumentation asset management functionality
- Replace all or portion of instrument wiring.

## Selected Configuration

---

- Replace Controllers, I/O, Power Supplies and HMI's with current or alternate manufacturers most current product for North Riverfront, 1<sup>st</sup> Ave, Convention Center and Main Plant (Existing Bailey Infi90 systems)
  - Emerson Delta V was selected.
- Retain existing Allen Bradley control systems at Macy's and Foster House Plants.
- Retain existing Fisher ROC/Single Loop Controller control system at Baker Plant
- Retain existing fiber optic communications with Baker, Macy's and Foster House
- Switch to DSL communications for 1<sup>st</sup> Ave, Convention Center and Fairview Plants
- Upgrade fiber optics communications interfaces at all connected plants
- Replaced all I/O wiring back to local equipment control panels and majority of standalone instruments

## Overview – Selected Configuration



## Project Implementation – Schedule

---

- Initial discussions started in 2009
- Development of project scope was started and stopped multiple times over the next 6 years due to budget constraints and lack of consensus on scope.
- October of 2014 consultant hired to develop project scope
- Proposals solicited fall of 2015
- DCS vendor awarded February of 2016
- System configuration, cabinet construction and FAT complete September of 2016
- Operator training completed in August of 2016
- Phase I - NRP and Main Plant HMI's installation started September of 2016
- Phase II – 1<sup>st</sup> Avenue, Convention Center and Foster House plants installation started November of 2016
- Phase III – Main plant installation started March of 2017.
- Phase IV installation – Fairview Riverside started June of 2017
- Project complete December 2017



## Project Implementation – Key Aspects

---

- Utilize 3<sup>rd</sup> Party Consultant to Help Evaluate Current and Future Needs and Support Project Development and Construction
  - Conduct stakeholder meeting
  - Evaluate Potential Vendors
  - Prepare Project Requirements Document and Procurement Specification
  - Provide Technical Support for Design, Installation and Commissioning
  - Develop Project Implementation Plan
- Comprehensive Bid Evaluation Matrix/Scoring
  - Equipment Cost
  - Configuration Cost
  - Schedule
  - Functionality
  - Life Cycle
  - Support Capabilities
  - Support Cost
  - Training Cost

## Project Implementation – Key Aspects

---

- Stakeholder meetings to finalize project scope and create buy-in
- Award, Develop and Approve Final Hardware and Configuration Scope Prior to Developing Installation Bid Documents
- Utilize phased approach to installation and commissioning
  - Avoid overburdening plant operators and I&C staff
  - Identify unknown/missed items so they can be corrected before the next phase.
- Complete comprehensive Operator training using simulator with actual configuration
- Fully document existing system components and wiring to remain.

## Project Implementation Plan Elements


---

- Stakeholder meetings to final and achieve consensus on project scope
- Prepare project hardware and configuration procurement specifications
- Hardware and configuration bid solicitation, review and selection
- Hardware and configuration submittal review and acceptance
- Prepare project installation specifications
- Installation bid solicitation, review and selection
- Comprehensive off-site Operating training
- Comprehensive Factory Acceptance Testing
- Phased implementation approach
- Complete installation, commissioning and operational break-in period for each phase before commencing next phase
- Small independent North River Front Plant first
- 1<sup>st</sup> Ave Satellite , and Convention Center Plants next
- Main Plant and Fairview Riverside last

## Project Cost

### Project Cost Breakdown

Total Project Cost - \$1,778,000





## System Size

Hardware	Qty	I/O	Qty
Redundant Pairs Controllers	6	Analog I/O	617
Analog I/O Modules	67	Discrete I/O	397
Discrete I/O Modules	66	Pseudo Analog I/O	90
Redundant Pairs Power Supplies	6	Pseudo Discrete I/O	28
Quad Screen Operator Workstations	2		
Dual Screen Operation Workstations	4		
Engineering/DAQ Workstations	2		
Graphics	Qty	Control Points	Qty
Process Overview	5	Analog Indicators	351
Process System	20	Digital Indicators	247
Process Unit	22	Analog Control Loops	131
		Discrete Control Modules	87
		Custom Control Modules	13

## Project Lessons Learned – What We Did Right

---

- Utilize knowledgeable 3<sup>rd</sup> party consultant to guide all phases of the project
- Develop, award and approve final hardware and configuration design prior to developing installation bid documents
- Complete comprehensive off-site operator training in advance of initial implementation
- Utilize phased approach to prevent overburdening operations personnel and to identify unknown/missed items to be corrected before next phase
- Involve as many plant operations personnel as possible in system commissioning.
- Accurately document and label existing I/O and wiring and terminations

## Lessons Learned – What We Did Wrong

---

- Assign project manager (preferably 3<sup>rd</sup> party) to take the lead on developing initial draft scope vs trying to develop scope by committee.
- Start with one on one interviews with various stakeholders
- Don't overload stakeholders with too much information – break scope into distinct smaller categories and reach consensus in steps.
- Start discussions with 3<sup>rd</sup> party communication vendors as soon as possible and leave sufficient time in schedule to secure service

---


Thank You

Questions?




# Project Network Configuration

## WAN – Communication Redundancy




# Project Network Configuration

## DeltaV Architecture Diagram – Final Phase of Phased Implementation




# Project Network Configuration



## Installation Pictures

---

### EXISTING SYSTEM





## Installation Pictures


---

### NEW SYSTEM




# Installation Pictures

EXISTING SYSTEM GRAPHICS



NEW SYSTEM GRAPHICS



# Installation Pictures

---

**EXISTING SYSTEM**



**NEW SYSTEM**

